

1993

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Luce

(County)	Located in:	Corner Code #
1. Public Land Survey	T45N R 10W	C-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Filed 12-22 A.D., 1993

At 10:00 o'clock A.M.

File No. 499 499

Keith R. Waters  
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

1. Keith R. Waters in a field survey on September 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-4 1/4 Corner Common to Sections 7 & 8, T45N, R10W

Original ties to post:  
Fir 6, S60°E 13 links  
Fir 5, N64°W 20 links

1977 - This corner is shown on MDOT Luce County right-of-way maps, page 6, at station 302+44.41, 17.63 feet south of tangent on Highway M-28.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4

This corner is being perpetuated as part of the Luce County Remonumentation Program. Found a 1" solid iron in asphalt approach to County Road 425 on the south side of Highway M-28. Position checks within 0.15' of found highway monumentation at P.I. station 296+55.74 and at P.T. station 308+95.24. Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4

Corner is a 1" solid iron in asphalt approach to County Road 425, on the south side of Highway M-28. Corner is 28'± east of centerline of County Road 425, 8" below pavement surface. Witnesses:

- 7" Aspen, S10°E 72.68'
- Power Pole (NY3-32M), S40°W 93.96'
- Power Pole (NY3-32), N14°W 114.04'
- 3/4" Drill Hole in Top of Concrete Headwall, S27°W 23.70'

Note: Unless noted otherwise, distances are to a nail and tag in the side of witness object. Aspen is blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142

