

MAR 13 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Luce County Remonumentation Corner

For corners in

Luce County Located in: Corner Code #
1. Public Land Survey T45N R10W D-5
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

LUCE COUNTY SECTION
REGISTER OF DEEDS
Recorded
Liber 3 Page 905
02-08-2000 13:01:39
Kathy S. Mahar
Kathy S. Mahar, Register
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column D and row 5.

I, Keith R. Waters, in a field survey on November 12, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5 1/4 Corner Common to Sections 8 & 17, T45N, R10W

1849 - Original corner established by William Ives.

Witnesses: Yellow Birch 7, N23°W 10 links - Cedar 8, S03°E 18 links.

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being reestablished as part of the Luce County Remonumentation Program.

Found no evidence of the original corner. Reestablished corner at the record GLO distance (40 chains) east of the section corner at C-5, on a line towards the computed position of the section corner at E-5, which falls in Kak's Lake. The section corner at E-5 was computed at a pro-rated location according to the original GLO notes between the meander corners on the north and south sides of Kak's Lake. (2029.5 feet GLO, 2002.9 feet measured, between said meander corners). (Note: The original GLO notes do not show an east-west distance to the theoretical section corner in Kak's Lake).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 1/2" x 18" rebar with a stamped aluminum Luce County Remonumentation cap at the corner location.

Witnesses:

6" Spike, S24°W 3.32'

6" Spike in Northwest Corner of a 24" Aspen Stump, N86°E 3.63'

1/2" Rebar with cap #33142, N75°W 17.43'

1/2" Rebar with cap #33142, S03°W 16.93'

1/2" Rebar with stamped aluminum Luce County Remonumentation Cap, EAST 1574.29'

(Witness Corner to Meander Corner Sections 8/17, on West Side of Kak's Lake)

(Note: No other suitable witness objects nearby).



Signed by Keith R. Waters

Date 12-29-99

Surveyor's Michigan License No. 33142