

1993

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

(County)	Located in:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>10W</u>	E-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Filed 12-20-93 A.D.; 1993

At 10.00 o'clock A.M.

File No. 486

Kathy S. Mahan
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Keith R. Waters September 93

I, Keith R. Waters, in a field survey on September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-8 1/4 Corner Common to Sections 20 & 21, T45N, R10W

Original ties to post: 1978 - This corner is shown on a survey recorded by Thomas M. Kelly, R.L.S. 24599, in Book 1, Page 23, Luce County Recorded surveys, as a 1/2" iron with cap 24599. Ties: 9" Maple, S77°E, 4" Maple, S30°W 29.14, and Twin 10" Maple, S55°E 14.72.
1983 - Corner is shown on a survey recorded by Eino Sainio, P.S. 7873, in Book 1, Page 61, as a 1/2" iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8
This corner is being perpetuated as part of the Luce County Remonumentation Program. Found a 1/2" iron with smashed plastic cap in approximate centerline of north-south gravel road (County Road 447). Position checks to lone remaining tie from Kelly survey (4" Maple). Corner is approximately 10 feet south of a fence line to the east. Accepted corner as found and placed a 3 1/4" aluminum Luce County cap on iron.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8
Corner is a 1/2" rebar with 3 1/4" aluminum Luce County cap in approximate centerline of County Road 447. Witnesses:

- 10" Sugar Maple, N88°E 61.46'
- 7" Sugar Maple, S26°W 29.22'
- 6" Sugar Maple, S52°W 25.44'
- 5" Yellow Birch, N83°W 29.12'

Note: Distances are to a nail and tag in the side of tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142