

1993

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Luce

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>10W</u>	<u>F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Filed 12-22 A.D., 1993

At 10:00 o'clock A.

File No. 487

*Keith R. Waters*  
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-7 1/4 Corner Common to Sections 16 & 21, T45N, R10W

Original ties to post:  
Elm 7, N66°W 19 links  
Fir 7, S76°E 19 links

1984 - This corner is shown on a survey recorded by Eino Sainio, P.S. 7873, in Book 1, Page 78, of Luce County recorded surveys, as a PK nail.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7

This corner is being perpetuated as part of the Luce County Remonumentation Program. Found a PK nail in the westbound lane of east-west asphalt road (County Road 458). Position fits with other found irons as shown on Sainio survey. Corner is 1.17' north of straight line between Section corners east and west. Corner measures 2651.51 to Section corner west and 2649.32 to Section corner east. Corner is approximately 3.5 feet west of a fence line to the south. Accepted corner location as found and replaced PK nail with a 1/2" iron and 3/4" aluminum Luce County cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7

Corner is a 1/2" rebar with 3/4" aluminum Luce County cap 6 feet north of centerline of County Road 458. Witnesses:

- 12" Cedar, N47°E 53.03'
- 7" Cedar, NORTH 41.58'
- 6" Cedar, N33°W 52.52'
- 22" Cedar, N64°W 83.74'

Note: Distances are to a nail and tag in the side of tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142