

MAR 13 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Luce County Remonumentation Corner

SECTION

For corners in

Luce County Located in: Corner Code #
1. Public Land Survey T45N R10W G-2
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

LUCE COUNTY REGISTER OF DEEDS
Recorded
Liber 3 Page 898
02-08-2000 12:59:55
Kathy S. Major, Registrar
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column G and row 2.

I, Keith R. Waters, in a field survey on December 7, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-2 1/4 Corner Common to Sections 3 & 4, T45N, R10W

1849 - Original corner established by William Ives.

Witnesses: Spruce 4, S24°W 04 links - Tamarack 4, S52°E 17 links.

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being reestablished as part of the Luce County Remonumentation Program.

Found no evidence of the original corner. Reestablished corner by single proportionate measurement on line between the section corner on the township line at G-1 to the north and the section corner at G-3 to the south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 1/2" x 18" rebar with a stamped aluminum Luce County Remonumentation cap at the corner location, which falls approximately 30 feet west of the centerline of Luce County Road 405 (Dollarville Road).

Witnesses:

Nail and tag #33142 in 12" blazed Twin Jack Pine, N66°E 101.90'

Nail and tag #33142 in 6" blazed Spruce, S72°E 81.05'

Nail and tag #33142 in 14" blazed Spruce, N52°W 46.51'

Nail and tag #33142 in 14" blazed Spruce, S43°W 62.40'



Signed by Keith R. Waters

Date 12-29-99

Surveyor's Michigan License No. 33142