

MAR 13 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Luce County Remonumentation Corner

SECTION

For corners in

| Luce County                        | Located in: | Corner Code # |
|------------------------------------|-------------|---------------|
| 1. Public Land Survey              | T45N R10W   | G-4           |
|                                    | T R         |               |
|                                    | T R         |               |
|                                    | T R         |               |
| 2. Property Controlling in Section | S T R       |               |
|                                    | S T R       |               |
| 3. Miscellaneous Property in Sec.  | S T R       |               |
|                                    | S T R       |               |
| 4. Lot No. , Recorded Plat         |             |               |
| 5. Private Claims                  |             |               |

LUCE COUNTY  
REGISTER OF DEEDS  
Recorded  
*Liber 3 Page 896*  
02-08-2000 12:59:29  
*Kathy S. Mahar*  
Kathy S. Mahar, Register  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

I, Keith R. Waters, in a field survey on December 7, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4 1/4 Corner Common to Sections 9 & 10, T45N, R10W

1849 – Original corner established by William Ives.

Witnesses: Beech 12, S65°E 16 links – Sugar 12, N45°W 24 links.

1966 – Michigan State Highway Department, set a 3/4" rod in a monument box.

1990 – Neil E. Hill, P.S. 27447, Michigan Department of Transportation Surveyor, LCRC recorded in File 423, Luce County Corner Records. Found and accepted a 3/4" iron pin in a monument box. Witnesses:

- Power Pole, S15°W 105.04'
- Top Center R/W Marker, S55°W 175.07'
- US BM TT26S, N30°E 71.79'
- 9" Red Pine, N55°E 122.82'

1993 – Dennis R. Destrampe, P.S. 18983, LCRC recorded in Liber 2, page 466, Luce County Corner Records. Found and witnessed found 3/4" pin in monument box. Reset 5/8" pin in monument box after construction. Witnesses:

- Power Pole, S15°W 105.04'
- Top Center R/W Marker, S55°W 175.07'
- 9" Red Pine, N55°E 122.82'
- Stop Sign, N12°W 82.48'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Luce County Remonumentation Program. Found a 5/8" iron pin in a monument box in the intersection of Luce County Road 405 and Highway M-28. Also found three of the record witness objects called for in the above mentioned 1993 LCRC, the red pine is gone. Accepted corner as found and added additional witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 5/8" iron pin in a monument box at the corner location, which falls in the Luce County Road 405 and Highway M-28 intersection. Witnesses:

- Nail and MDOT tag in Power Pole, S15°W 105.04'
- Top Center of Right-of-Way Marker, S55°W 175.07'
- Stop Sign, N12°W 82.48'
- Nail and tag #33142 in Light Anchor Pole, N28°E 133.51'
- Nail and tag #33142 in Power Pole, S47°E 139.85'



Signed by Keith R. Waters

Date 12-29-99

Surveyor's Michigan License No. 33142