

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Luce

| (County) | Located In: | Corner Code # |
|---------------------------------------|---------------------------|---------------|
| 1. Public Land Survey | T <u>45N</u> R <u>10W</u> | G-6 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Filed 12-22 A.D., 1993

At 10:00 o'clock A. M.

File No. 98 488

Keith R. Waters
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on September, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6 1/4 Corner Common to Sections 15 & 16, T45N, R10W

Original ties to post:
Cedar 18, S60°E 25 links
Cedar 6, N30°W 20 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6

This corner is being perpetuated as part of the Luce County Remonumentation Program. Found a PK nail with tag, Eino Sainio, L.S. 7873, in the southbound lane of north-south asphalt road (County Road 405). Also found blazed and scribed cedars to the east and northwest. In talking with Eino, he indicated that he established position using notes from surveyor Harold C. Lawrence, dating back to the 1930's or 1940's. Corner is also shown on a drawing done by MDOT surveyor Neil Hill, P.S. 27447. Distance to section corner north is 2627.15' and distance to section corner south is 2649.89'. Accepted corner as found and replaced PK nail with a 1/2" iron and 3 1/4" aluminum Luce County cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6

Corner is a 1/2" rebar with 3 1/4" aluminum Luce County cap 7.5 feet west of centerline of County Road 405. Witnesses:

- Anchor Pole (13X), N35°E 80.92'
- 9" Cedar, S88°E 50.36'
- 5" Cedar, S88°W 76.10'
- 10" Cedar, N64°W 53.76'

Note: Distances are to a nail and tag in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

