

1993

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Luce

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>10W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Filed 12-22 A.D.; 1993

At 10:00 o'clock A.M.

File No. 489

Keith R. Waters
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-7 Corner Common to Sections 15,16,21 & 22, T45N, R10W

Original ties to post:
Beech 12, S39°E 08 links
Sugar 8, N57°W 40 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7
This corner is being perpetuated as part of the Luce County Remonumentation Program. Found a railroad spike in southbound lane of north-south asphalt road (County Road 405) at the intersection of County Road 458 to the west. Spike was set by Eino Sainio, P.S. 7873, using notes from surveyor Harold C. Lawrence, dating back to the 1930's or 1940's. After talking to Eino, accepted corner as found. Replaced railroad spike with a 1/2" iron and 3 1/4" aluminum Luce County cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7
Corner is a 1/2" rebar with 3 1/4" aluminum Luce County cap 2.6 feet west of centerline of County Road 405, 1.5 feet south of centerline of County Road 458 to the west. Witnesses:

- Power Pole (NY2-21-M), S74°E 44.30'
- 8" Red Maple, S75°W 105.36'
- Power Pole (NY2-21), N66°W 84.64'
- Fence Post, N28°W 86.28'

Note: Distances are to a nail and tag in the side of the witness object. Maple is not blazed. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142