

1993 LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Luce

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey | T | 45N | R | 10W | G-8 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Filed 12-22 A.D., 1993

At 10:00 o'clock A.M.

File No. 49 490

Keith R. Waters
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Keith R. Waters September 93

I, Keith R. Waters, in a field survey on September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-8 1/4 Corner Common to Sections 21 & 22, T45N, R10W

Original ties to post:
Fir 7, S22°E 20 links
Beech 7, N55°W 15 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8

This corner is being perpetuated as part of the Luce County Remonumentation Program. Found a spike with i.d. tag, Eino Sainio, L.S. 7873, in centerline of north-south asphalt road (County Road 405). In talking with Eino, he indicated that he established position using notes from surveyor Harold C. Lawrence, dating back to the 1930's or 1940's. Position also fits with a DNR section subdivision sketch of Section 22, done by Billy Buckler, P.S. 8887, dated 2-2-77. Corner is approximately 13 feet north of a fence line to the west, which is also consistent with DNR field notes. Accepted corner as found and replaced spike with a 1/2" iron and 3 1/4" aluminum Luce County cap. (Distance to section corner north is 2647.48' and distance to section corner south is 2650.78').

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8

Corner is a 1/2" rebar with 3 1/4" aluminum Luce County cap in centerline of County Road 405. Witnesses:

- 8" Beech, N50°E 62.32'
- 7" Ironwood, EAST 58.06'
- 11" Yellow Birch, S50°E 67.28'
- Power Pole (NY2-28), N87°W 33.06'

Note: Distances are to a nail and tag in the side of the witness object: Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142