

1993

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Luce

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>10W</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Filed 12-22 A.D.; 1993

At 10:00 o'clock A.M.

File No. 499 497

Keith R. Waters
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on September, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-10 1/4 Corner Common to Sections 27 & 28, T45N, R10W

Original ties to post:
Yellow Birch 6, N47°W 16 links
Beech 7, S27°E 33 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10

This corner is being perpetuated as part of the Luce County Remonumentation Program. Found a spike with i.d. tag, Eino Sainio, L.S. 7873, in north-south asphalt road (County Road 405). Position fits with a DNR section subdivision sketch of Section 27, done by Billy Buckler, P.S. 8887, dated 1-25-77. Corner is on line between Section corners 2643.78 feet south and 2654.09 feet north, at a fence line to the west. Accepted corner position as found and replaced spike with a 1/2" rebar and 3 1/4" aluminum Luce County cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10

Corner is a 1/2" rebar with 3 1/4" aluminum Luce County cap in centerline of County Road 405 at fence line to west. Witnesses:

- 8" Sugar Maple, N50°W 79.36'
- 5" Sugar Maple, N85°W 73.46'
- 7" Sugar Maple, S59°W 71.05'
- 13" Sugar Maple, S37°E 71.13'

Note: Distances are to a nail and tag in the side of tree. Except for 13" sugar maple, trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142