

1993

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

(County)

Located In:

Corner Code #

- 1. Public Land Survey T45N R 10W G-11
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

Filed 12-22 A.D., 1993

At 10:00 o'clock A.M.

File No. pg 500

Keith R. Waters
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Keith R. Waters in a field survey on September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-11 Corner Common to Sections 27,28,33, & 34, T45N, R10W

Original ties to post: 1976 - This corner is shown on a survey recorded by James H. Granger, P.S. 16041, in Book 1, Page 25, Luce County recorded surveys, as a P. Pole, N31°W 55.5' Prop. Iron, East 43.0' 12" Ash, S27°E 89.2'

Y. Birch 15, N43°E 34 links
 Y. Birch 6, S59°W 34 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11
 This corner is being perpetuated as part of the Luce County Remonumentation Program. Found a spike with i.d. tag, Eino Sainio, L.S. 7873, in centerline of north-south asphalt road (County Road 405). Position checks with power pole and 1/4 corner 1/2 mile south as shown on Granger survey. Position also checks with a DNR section subdivision sketch of Section 34, done by Billy Buckler, P.S. 8887, dated 6-21-76. Accepted corner position as found and replaced spike with 1/2" iron and 3/4" aluminum Luce County cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11
 Corner is a 1/2" rebar with a 3/4" aluminum Luce County cap in the centerline of County Road 405. Witnesses:

- Power Pole, N84°E 39.93'
- 10" Sugar Maple, S72°W 69.92'
- 6" Sugar Maple, N74°W 63.21'
- Power Pole, N36°W 55.21'

Note: Distances are to a nail and tag in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters Date 12-20-93

Surveyor's Michigan License No. 33142