

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Luce County Remonumentation Corner

MAR 13 2000

For corners in

SECTION

Luce County	Located in:	Corner Code #
1. Public Land Survey	T45N R10W	I-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

LUCE COUNTY
REGISTER OF DEEDS
Recorded
Liber 3 Page 894
03-08-2000 12:59:05
Kathy S. Mahar
Kathy S. Mahar, Registrar
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on December 7, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-2 1/4 Corner Common to Sections 2 & 3, T45N, R10W

1849 - Original corner established by William Ives.

Witnesses: Cedar 9, S86°W 17 links - Spruce 6, S68°E 07 links.

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Luce County Remonumentation Program. Found a bent 1 1/4" i.d. iron pipe next to a broken off wood post. The found pipe is 2657.4 feet from the section corner at I-3 to the south (GLO distance is 2640 feet), 2555.4 feet from an original section corner on the township line at I-1 to the north (GLO distance is 2564.8 feet), and is 11.5 feet west of a straight line between said section corners. Accepted the found pipe as best evidence of the corner location. Set a 1/2" rebar and stamped aluminum Luce County Remonumentation cap at the base of the found pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 1/2" x 18" rebar with a stamped aluminum Luce County Remonumentation cap at the corner location, at the base of a found pipe, next to a broken off wood post.

Witnesses:

Nail and tag #33142 in 6" blazed Cedar, S82°W 2.75'

Nail and tag #33142 in 7" blazed Cedar, S14°W 23.13'

Nail and tag #33142 in 8" blazed Tamarack, N74°E 16.20'

Nail and tag #33142 in 9" blazed Cedar, N18°E 24.37'



Signed by Keith R. Waters

Date 12-29-99

Surveyor's Michigan License No. 33142