

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S <u>22</u> T <u>45N</u> R <u>10W</u>	<u>13</u>
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

I, Stephan J. Szyszkoski, in a field survey on July 30, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (13-Sec. 22) Southeast 1/16 corner Section 22. 1978 - established by Billy D. Buckler RLS in an erroneous position. Found no further record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (13-Sec. 22) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The position for the corner falls in Mervin Lake and was not monumented. Established two Witness Corners: 265.0' North of the corner on the north shore and 900.0' West of the corner on the west shore, both set on respective 1/16 lines. The 1978 Buckler monument on the north side of the lake was removed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap for a Witness Corner on the North shore of Mervin Lake 265.0' north of the corner position and on the 1/16 line. Set measuring nails in: 14" Maple N30W 28.1' mrkd "WC BT" 6" Maple N67E 18.52' do 14" Maple N85E 28.25' do 7" Hemlock S05W 8.25' do Bearings are magnetic. Distances are to nail and tag in side of tree.	Set 1"IDx32" I.pipe with 4" alum. MDNR cap for a Witness Corner on the West shore of Mervin Lake 900.0' west of the corner position and on the 1/16 line. Set measuring nails with MDNR tags in: 7" Hemlock East 17.87' mrkd "WC BT" 20" Hemlock S43E 37.3' do 15" Hemlock N50W 22.5' do 5" Hemlock S13W 5.75' do Bearings are magnetic. Distances are to nail with tag in side of tree.
---	---

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4			3		2			1
3													
4	7		8		9			10		11			12
5													
6	18		17		16			15		14			13
7													
8	19		20		21			22		23			24
9													
10	30		29		28			27		26			25
11													
12	31		32		33			34		35			36
13													

Signed by Stephan J. Szyszkoski Date 9/11/07



Surveyor's Michigan License No. 33986