

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 25 T 45NR 10W	15
	S 25 T 45NR 10W	10
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 23 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (15-Sec. 25) West 1/16 corner between Sections 25 and 36. Not established in the original survey. Recorded in 1970 by Billy D. Buckler RLS who found and accepted a 1" iron pipe.
- (10-Sec. 25) South 1/16 corner between Sections 25 and 26. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (15-Sec. 25) Established the corner midway and on the Section line between Section corner 1356.27' west and Quarter corner 1356.27' east. The 1" iron pipe previously recorded by Mr. Buckler was recovered as noted below and was not accepted as marking the position for the corner.
- (10-Sec. 25) Established the corner midway and on line between Quarter corner 1325.18' north and Section corner 1325.18' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (15) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
8" Maple S35W 8.04' mrkd "W1/16 BT"
13" Maple S41E 7.34' do
9" Maple N44W 8.6' do
13" Maple N44E 40.15' do
Fd. a 1" pipe West, 38.59' distant.
Bearings are magnetic. Distances to trees are to nail with tag. | (10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
12" Maple N54W 12.52' mrkd "S1/16 BT"
10" Maple N05E 17.5' do
12" Maple S88E 20.48' do
12" Maple S10W 19.98' do
Fd. an angle iron East 47.59' distant.
Bearings are magnetic. Distances to trees are to nail with tag. |
|---|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 1/16/07

For the Michigan Department of Natural Resources, Office of Land and Facilities