

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	S 22	T 45N R 10W	H8
2. Property Controlling in Section	S 22	T 45N R 10W	8
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

H8 Jul 30 2007
 8 Jun 26 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H8) Center of Section 22. 1978 - established by Billy D. Buckler RLS in an erroneous position. Found no further record.

(8-Sec. 22) West 1/16 corner, Section 22. 1978 - established by Billy D. Buckler RLS in an erroneous position. Found no further record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners. From the position thus established I found the 1978 Buckler monument N87E 18' distant and removed it.

(8-Sec. 22) Established the corner midway and on a straight line between Quarter corner 1316.68' west and Center of Section 1316.68' east. From the position thus established, I found the 1978 Buckler monument N57E 11' distant and removed it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.

Set measuring nails with MDNR tags in:

10" twin Maple N35W 3.14' mrkd "CS BT"

18" W.Pine S78E 10.3' do

11" Maple S45E 37.1' do

10" Maple S20W 5.24' do

Bearings are magnetic. Distances are to nail with tag in side of tree.

(8-Sec. 22) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.

Set measuring nails with MDNR tags in:

15" Maple S18E 14.22' mrkd "W1/16 BT"

14" Maple S74E 25.55' do

15" Maple N12W 20.93' do

13" Maple N55E 28.6' do

Bearings are magnetic. Distances are to nail with tag in side of tree.

Signed by

Stephan J. Szyszkoski



Date

9/11/07

Surveyor's Michigan License No. _____

33986