

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 23 T 45N R 10W	12
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 05/27/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(12-Sec. 23) South 1/16 corner, Section 23. 1975 - Established by Billy D. Buckler RLS midway between Center of Section 23 and South 1/4 corner of Section 23. Set 1" ID Iron pipe with 4" aluminum cap. 8" B. Cherry S63W 7.1', 20" Hard Maple N24E 22.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12-Sec. 23) The 1977 monument was found disturbed, laying on the ground, aluminum cap gone, extracted by persons unknown. Recovered the hole left at the corner position, it being at record bearing and distance from the remains of the 1977 bearing trees. The B.Cherry is dead and down, the Hard Maple is a cut stump. Drove a new monument into the hole at the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Maple S24W 16.74' mrkd "S1/16 BT"
 18" Maple N25W 9.35' do
 9" Maple S82E 18.4' do
 9" Cherry S77W 13.35' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 02/17/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities