

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

1 Corner

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 11 W.	G-7
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. W.	
4. LOT NO. RECORDED PLAT.		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Billy D. Buckler**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-23, 1967, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-7 S.E. Section Corner of Section 16. O.B.T.'S: Wood Post. Beech 14, S36⁰W, 52 lks. & Fir 9, N33⁰E, 16 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-7 This corner re-witnessed as set by Harold Lawrence, R.L.S. Found pipe buried in North edge of woods road with two 2" iron pipes bearing N45⁰E, 45.1' and S45⁰W, 45.1'. Found squared and scribed Cedar Post 2.0' N.E. of corner. Corner found by C. Taylor, Newberry.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 Iron Pipe, Buried. Bearings: 14" Soft Maple, S38⁰E, 33.6'
13" Y. Birch, N40⁰E, 16.2'

SIGNED BY

Billy D. Buckler

Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

DATE 9-25-84

