

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luca _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling In Section	S <u>35</u> T <u>45N</u> R <u>11W</u>	<u>15</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Oct 12 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
(15-Sec. 35) West 1/16 corner between Sec. 2 T44N-R11W and Sec. 35 T45N-R11W. Corner not established in the original survey. Corner established in 1967 by Billy D. Buckler RLS: " This corner established midway and on line bet. 1/4 cor. to east and Sec. Cor. to west. Corner monument 1" pipe with 4" aluminum cap. 6" N. Maple N20W 17.0', 9" H. Maple S25W 13.6".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15-Sec. 35) Recovered the 1967 monument as described, a 1" ID iron pipe capped with a 4" dia. cast aluminum MDNR tablet, in good condition, and at record bearing and distance from the 1967 witness trees, both in good condition. My measurements show the monument to be 2.04' West and 3.96' South of the record position. I accept the monument as a careful and faithful determination of the position of the corner. I made new markings on the 1967 witness trees and marked two new accessories as described below. Corner recovered and re-witnessed by T.Stark and M.Feldpausch, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) Fnd 1" pipe with 4" MDNR cap.  
Blazed, scribed, and set measuring nails  
in the following:  
12" Maple S25W 13.0' "W1/16"(1967 wit)  
10" Maple N17W 17.4' "W1/16"(1967 wit)  
8" Maple S67E 29.95' "W1/16 BT"  
12" Maple N64W 25.1' "W1/16 BT"  
N-S rd. is 16' West. Placed a 4"  
squared and scribed post adjacent.  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12/28/98

For the Michigan Department of Natural Resources - Forest Management Division