

#36

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luca

_____	Located in:	Corner Code #
(County)		
1. Public Land Survey	T ^{45N} R ^{11W}	68
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Oct 23 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
(68) Quarter corner common to Sections 21-22. Corner reestablished in 1967 by Billy D. Buckler, RLS "midway and on line bet. two Sec. Cors. No evidence of original corner. Corner lies 1 1/2 chs. west of an old woods road. Placed 1" pipe with 4" aluminum cap. 7" Hard Maple N55E 20.2', 7" Hard Maple S80W 26.1'".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(68) Found Buckler's 1967 monument as described, in good condition, and at record bearing and distance from his witnesses, both in good condition. Left the monument in place, marked new BH blaze on the witnesses, and made two new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(68) Found 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails
in the following:

10" N. Maple N55E 20.45' "1/4S"
12" N. Maple S80W 26.4' "1/4S"
6" N. Maple N48W 7.8' "1/4S NBT"
5" N. Maple S04E 4.35' "1/4S NBT"

Placed 5" square and scribed cedar post adjacent. Placed location poster 75' east on N-S trail. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 2-1-96



For the Michigan Department of Natural Resources - Forest Management Division