

#35

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Luce

(County)	Located In:	Corner Code #
1. Public Land Survey	T 45R 11W	67
	T 45R 11W	68
2. Property Controlling in Section	T R	
	T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Oct 23 1995

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(67) Corner common to Sections 15-16-21-22. Corner recovered and re-monumented in 1967 and recorded in 1984 by Billy D. Buckler, RLS. Buckler found iron pipe buried in north edge of road with 2" iron pipe witnesses N45E and S45W, both 45.1' distant. Buckler's NBTs: 14" Soft Maple S38E 33.6', 13" Y. Birch N40E 16.2'.

(68) Quarter corner common to Sections 20-21. Corner recorded in 1979 by Billy D. Buckler, RLS: "Replaced corner from one Cedar stump, a possible bearing tree. Location fits cors. North and South. Placed 1" pipe with 4" aluminum cap, new bearings: 9" Cedar S44E 26.8', 6" W. Spruce N25E 1.6'".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(67) Found 2" iron pipe, buried in north edge of road as described in 1984. Both Buckler's NBTs are in good condition with blazes overgrown. The iron pipe witnesses were found as described above. Re-blazed the NBTs, placed measuring nails with tags in them, and marked two new witnesses as described below. Left the monument in place. This corner is being rerecorded to update the accessories. This area is will be logged in the near future.

(68) Found and accepted Buckler's monument as described, in good condition, and at record bearing and distance from the W. Spruce NBT. The Cedar NBT was found dead and down. Left the monument in place, marked a new BK blaze and set measuring nail with tag in the spruce, and marked three new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(67) Found 2" iron pipe, buried. Blazed, scribed, and set measuring nails in the following new bearing trees:  
16" S. Maple S38E 34.0' "S22"  
16" Y. Birch N40E 16.55' "S15"  
12" Maple S82W 42.3' "S21 NBT"  
12" Maple S79E 28.2' "S22 NBT"  
Placed a 5" squared and scribed cedar post adjacent. Bearings are magnetic.

(68) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails with tags in the following:  
8" W. Spruce N25E 1.95' "1/4S"  
12" W. Birch N35W 14.8' "1/4S NBT"  
5" W. Spruce N16E 14.55' "1/4S NBT"  
6" Balsam N85E 12.3' "1/4S NBT"  
Placed 3" squared and scribed cedar post adjacent. Placed location poster 110' north at E-W trail. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 2-1-96  
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division