

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45N N.R. 11W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 25, 26, 35, & 36

CORNER MONUMENT 1" pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8-2-67

WITNESSES TO CORNER..... 16" Hard Maple (S35 NBT) S32°W 15.5'



16" Hard Maple (S36 NBT) S70°E 33.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by proportionate distance bet. Secs. Cors; one mile west and one mile east and on line with old road, running east and west.

Found no evidence of original corner.

SURVEYOR'S SEAL

SIGNED Billy V. Buckler DATE 12-2-70
REGISTERED LAND SURVEYOR