

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Lace COUNTY
T 44-45N R 11W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 2-3-34-35

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 7-26-67

WITNESSES TO CORNER..... 6" cedar (S35 NBT) N59°E 4.2'



5" cedar (S2 NBT) S75°W 120'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at an old cedar post with all four original witnesses in evidence; a W. Pine bearing, N79°E 19 lks, tree broken off about 3' high; three cedar stumps, cut 16" high bearing N50°W 5 lks, S35°W 23 lks, and S45°E 24 lks. Found original faces with scribe marks on all stumps. Corner lies in a thick cedar swamp.

SURVEYOR'S SEAL

Billy D. Buckler

SIGNED

Billy D. Buckler

DATE

3-27-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
/ Forestry Div., Lansing