

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Luce COUNTY
T 45N R 11W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 22-23-26-27

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8-10-67

WITNESSES TO CORNER..... 11" W. Pine (S26 NBT) S15°E 13.4'



12" H. Maple (S23 NBT) N9°E 25.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by proportionate measure to corners; one mile north and south and to swamp edges. Corners to west. Distance east to an old township road checks well.

Corner lies 2.00 chs. north of Tee Lake.

SURVEYOR'S SEAL

Billy D. Buckler

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE

3-27-69

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
/ Forestry Div., Lansing