

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 11 W.	E-9 E-8
2. PROPERTY CONTROLLING IN SECTION 21	T. 45 N. R. 11 W.	10-Sec.21
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-13, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-9 Sec. Cor. 20-21-26-29, set by Wm Ives, D.S. in 1849.
Bearings were: Cedar 6", S42°W, 20 lks. and Spuce 5", N54°E, 14 lks.
- E-8 1/4 Corner between Sec's. 20-21, set by Wm Ives, D.S. in 1849.
Bearings were: Cedar 8", N31°W, 19 lks. and Fir 7", S25°E, 14 lks.
- 10-Sec.21 South 1/16 Corner on West side of Section 21.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- E-9 Replaced corner at a wood stake set by unknown surveyor. Distance from Sec. Cor. one mile North = 5,279.2'.
- E-8 Replaced corner from one Cedar stump, a possible bearing tree. Location fits cors. North and South.
- 10-Sec.21 Placed corner midway between 1/4 Corner to North and Sec. Cor. to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at all corners.

- E-9 New Bearings: 8" Tamarack, S76°E, 32.6' and 10" W. Pine, N77°W, 34.0'.
- E-8 New Bearings: 9" Cedar, S44°E, 26.8' and 6" W. Spruce, N25°E, 1.6'.
- 10-Sec.21 Bearings: 8" Cedar, S30°W, 6.8' and 6" Cedar, N15°E, 25.5'.

SIGNED BY Billy D. Buckler DATE 9-23-79
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____