

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <u>K.</u> , R. <u>11</u> W.	<u>G-5A</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10/6, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-5A Meander corner bet. Sec's. 15-16, on North shore of McCormick Lake. Record distance is 13.50 chs. South of North Section corner. Set by Wm Ives, D.S. in 1849. Bearings were: Y. Birch 8", N13°E, 38 lks. and W. Pine 16", S70°W, 07 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-5A Replaced corner from both original witnesses. Birch is dead but standing, scribe marks visible. Pine stump is tipped over.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5A Placed 1" pipe with 4" aluminium cap at corner.
 New Bearings: 24" White Pine, S75°W, 16.0' and 10" hemlock, N70°W, 8.4' and 12" white Pine, N01°W, 42.0'.


SIGNED BY Billy D. Buckler DATE 4-10-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____