

**SURVEY &
REMONUMENTATION**

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

Luce County Remonumentation Corner **LUCE COUNTY**

or corners in

Luce County

Located in:

Corner Code #

Public Land Survey

T45N R11W

B-3

T R

T R

T R

1. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous

S

T R

Property in Sec.

S

T R

4. Lot No. , Recorded Plat

5. Private Claims

REGISTER OF DEEDS

Recorded

Liber 3 page 763

02-24-1998 14:44:10

Karin B. Wendt Dep

Kathy S. Mahar, Register

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 12, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B-3) 1/4 Corner Common to Sections 6 and 7, T. 45 N., R. 11 W.

1849 William Ives set post in original survey.

Witnesses: 10" Sugar S 34° W 4 lks
10" Sugar N 08° E 25 lks

Could find no subsequent survey history on this corner in available public records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B-3) 1/4 Corner Common to Sections 6 and 7, T. 45 N., R. 11 W.

This corner is being perpetuated as part of the Luce County Remonumentation Program.

Could find no evidence of the original corner or subsequent restoration.

Reestablished corner position by single proportionate measurement between the section corners 1/2 mile West, 2574.00' (GLO), 2578.47' (meas) and 1/2 mile East, 2640.00 (GLO), 2644.58' (meas).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B-3) 1/4 Corner Common to Sections 6 and 7, T. 45 N., R. 11 W.

Corner is a 1/2" x 48" re-bar with a stamped aluminum Luce County Remonumentation cap. Corner is 300' North of an old East-West logging road and 1.0' South of a steel fence post.

Witnesses: 10" Maple N 24° W 20.36'
12" Maple N 28° E 13.05'
Twin 30" Basswood S 30° E 15.74'
16" Maple S 15° W 8.30'

Bearings are compass bearings, corrected for declination (8°W), all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by *William L. Karr*

Date *12/12/97*

Surveyor's Michigan License No. 27450

