SURVEY & REMONUMENTATION

APR 0 7 1998 CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Luce County Remonumentation Corner SECTION

or corners in

| .uce County | Located in: | | | Corner Code # |
|--------------------|-------------|----------------|---------------------|---------------|
| Public Land Survey | | T45N T T | R11W R R R | C-3 |
| in Section 8 | 6 | T T T | R R R R | |

LUCE COUNTY REGISTER OF DEEDS Recorded Page -1998 14:44:41 R Welcer. Mahar, Register wealt Dip REGISTER OF DEEDS

Register of Deeds Stamp & File Number

 Lot No. , Recorded Plat 5. Private Claims

, William L. Karr, in a field survey on December 12, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, ightharpoonup ⇒ and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by □ Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

H

Description of original monument and accessories and/or subsequent restoration:

(C-3) Section Corner Common to Sections 5, 6, 7 and 8, T. 45 N., R. 11 W.

1849 William Ives set post in original survey.

Witnesses:

10" Sugar N 48° E

36 lks


7" Sugar

S 62° W

37 lks

Could find no subsequent survey history on this corner in available public records.

∃. Description of corner evidence found and/or method applied in restoring or reestablishing corner:



Could find no evidence of the original corner or subsequent restoration. Reestablished corner by double proportionate measurement between the section corner 1 mile West and the 1/4 corners 1/2 mile North, South and East.

□. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-3) Section Corner Common to Sections 5, 6, 7 and 8, T. 45 N., R. 11 W.

Corner is a 1/2" x 48" re-bar with a stamped aluminum Luce County Remonumentation cap. The corner falls in a wooded area.

> Witnesses: Steel Fence Post North 1.00' 6" Maple N 08° E 50.681 8" Maple N 84° E 33.68 10" Yellow Birch S 52° E 17.02 10" Maple S 53° W 17.20'

Bearings are compass bearings, corrected for declination (6°W), all distances are to a nail and tag in the side of the witness object

Signed by

17/22/4

unless otherwise noted.