

SURVEY & REMONUMENTATION

APR 07 1998 LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

Luce County Remonumentation Corner

For corners in

Luce County

Located in:

Corner Code #

- | | | | |
|------------------------------------|---|-----------|-----|
| 1. Public Land Survey | | T45N R11W | C-6 |
| | | T R | |
| | | T R | |
| | | T R | |
| 2. Property Controlling in Section | S | T R | |
| | S | T R | |
| 3. Miscellaneous Property in Sec. | S | T R | |
| | S | T R | |
| 4. Lot No. , Recorded Plat | | | |
| 5. Private Claims | | | |

LUCE COUNTY
REGISTER OF DEEDS
Recorded

Liber 3 page 768
02-24-1998 14:45:00
Karen R. Wendt Sup
Kathy S. Mahar, Register
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 19, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C-6) 1/4 Corner Common to Sections 17 and 18, T. 45 N., R. 11 W.

1849 William Ives set post in original survey.

Witnesses:	8" B. Ash	N 70° W	3 lks
	7" Cedar	S 30° E	5 lks

Could find no subsequent survey history on this corner in available public records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-6) 1/4 Corner Common to Sections 17 and 18, T. 45 N., R. 11 W.

This corner is being perpetuated as part of the Luce County Remonumentation Program.

Found no evidence of the original corner. Reestablished the corner position by extending section line 7|8 South the record GLO distance (2640'). This position also agrees with a mean bearing of the section lines to the East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-6) 1/4 Corner Common to Sections 17 and 18, T. 45 N., R. 11 W.

Corner is a 1/2" x 48" re-bar with a stamped aluminum Luce County Remonumentation cap. The corner falls approximately 100' Northeast of the shore - shoreline runs NW-SE, and 132.00' North of a meander corner at the shore.

Witnesses:	6" Balsam	N 86° E	5.00'
	8" Cedar	S 04° W	22.95'
	6" Ash	N 88° W	11.56'
	15" Cedar	N 29° W	19.70'

Bearings are compass bearings, corrected for declination (6°W), all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by *W. L. Karr*

Date *2/19/98*

Surveyor's Michigan License No. 27450

