

1993

Luce County Remonumentation Program

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 45N R 11W D-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Filed 12-22 A.D., 1993

At 10:00 o'clock A.M.

Liber 2
File No. page 540

Fathy S. Mahan
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: (D-11) 1/4 Corner Sections 29 & 32, T45N-R11W

1849: Corner established by William Ives
Set 1/4 Section Post
Sugar 9 S 45 E 27 links
Sugar 8 North 13 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner perpetuated as part of the Luce County Remonumentation Program. Found a 1/2" iron, 2" below gravel road surface. Falls 5' East of road centerline and on centerline of road to East. Distance East to the Northeast corner of Section 32 is 2664.52'. Distance West to the Northwest corner of Section 32 is 2618.84'. Falls 19.72' South of a straight line between said Section Corners. Accepted corner position as found. Replaced found 1/2" iron with a 1/2" x 24" iron with a 3 1/4" diameter stamped aluminum cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" x 24" iron with a 3 1/4" diameter stamped aluminum cap, 6" below gravel road surface. Falls 5' East of centerline County Road 473 (North-South, gravel). Falls on centerline of County Road 468 to East (East-West, gravel).

Anchor Pole N42°E 42.35'
Power Pole NY3/167/20 S38°E 50.49'
10" Spruce S40°W 110.03'
Triple Cedar S76°W 92.94'
12" Cedar N70°W 102.86'

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column D and row 11.

Signed by

William L. Karr

Date

12/16/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination. Distances are to a nail with P.S. 27450 tag in side of witness objects unless noted.

