

PK: 10/2/97

**SURVEY &
REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970
Luce County Remonumentation Corner

APR 07 1998

For corners in

Luce County	SECTION	Located in:	Corner Code #
1. Public Land Survey		T45N R11W	E-7
		T R	
		T R	
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	
4. Lot No.			, Recorded Plat
5. Private Claims			

LUCE COUNTY
REGISTER OF DEEDS
Recorded
Liber 3 page 773
03-24-1998 14:46:00
Karen R. Wendt Dip
Kathy S. Mahar, Register
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 12, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-7) Section Corner Common to Sections 16, 17, 20 and 21, T. 45 N., R. 11 W.

1849 William Ives set a post in the original survey.
Witnesses: 10" Fir N 78° W 28 lks
12" Hemlock S 81° E 23 lks

19?? A sketch of the township obtained from the DNR shows this to be a corner perpetuated by Harold Lawrence.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-7) Section Corner Common to Sections 16, 17, 20 and 21, T. 45 N., R. 11 W.
This corner is being perpetuated as part of the Luce County Remonumentation Program.

Found no evidence of original corner. Found 2" pipe for corner with 2 witness pipes Northwest and Southeast at 45'. This is typical of monumentation established by J. Kinsey, County Surveyor, in the 1930's. Accepted pipe for section corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-7) Section Corner Common to Sections 16, 17, 20 and 21, T. 45 N., R. 11 W.

Corner is a 2" o.d. pipe projecting 18" above ground in wooded area. Set squared cedar post 2' North of corner.

Witnesses:	4" Maple	N 34° E	9.89'
	2" Pipe	S 45° E	45.12'
	12" Hemlock	S 32° E	12.51'
	11" Cedar	S 57° W	26.24'
	9" Maple	S 78° W	16.84'
	2" Pipe	N 45° W	44.90'

Bearings are compass bearings, corrected for declination (6°W), all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by *William L. Karr*

Date 12/22/97

Surveyor's Michigan License No. 27450

