

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 23 T 45N R 11W	1
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 04/21/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 23) West 1/16 corner between Sections 14 and 23. 1967 - Established by Billy D. Buckler RLS 33.0' South of a fence corner, in line with road to South and North of an East-West Road. Set 1.25"x20" iron pipe. 15" Hard Maple N24E 26.8', 9" Hard Maple West 33.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 23) Found the 1967 monument in good condition, on the North shoulder of the E-W road, 1 ft. below the ground surface, and at record bearing and distance from the 15" Hard Maple BT N24E. This BT is in poor condition and nearly dead. The BT Hard Maple West is gone. This corner is being recorded to update the accessories. It was not used to control any survey work this date.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Found 1.25" iron pipe 1ft. below ground on North shoulder of E-W road. Set measuring nail with MDNR tag in the side of:
 7" Maple N07W 35.28' mrkd "W1/16 BT"
 12" Maple N35W 36.96 do
 12" Maple N44E 33.91' do
 10" Maple S28E 81.05' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 02/17/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities