

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>45N</u> R <u>11W</u>	<u>17</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 08/05/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I7) Corner common to Sections 14-15-22-23. Corner previously approved 12/22/95 by Luce Co. Remonumentation Peer Review and recorded 2/29/96 in Liber 2, Luce County Land Corner Records, Page 669.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I7) Found the 2" pipe monument described on the 1995 record, in good condition and at record bearing and distance from the single remaining NBT of record: 10" (12" M) Sugar Maple N35W 7.82' (7.95' M). The other three NBTs noted in Part C of the 1995 record have been destroyed by road construction. Left the monument in place and made new accessories as described below. Accepted the 2" pipe monument of record. This corner is being recorded to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I7) Found 2" ID I.pipe with mushroomed top. The pipe falls 16 ft. north of centerline of a 20 ft. wide woods road. Set measuring nail with MDNR tag in the side of:

6" Maple N09E 6.95' mrkd "S14 NBT"
 6" Maple N56E 21.85' do
 10" Maple S05W 43.25' "S22 NBT"
 12" Maple N35W 7.95' mrkd "S15" fd WLK tag
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 02/17/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities