

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>45N</u> R <u>11W</u>	<u>H7</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7								●					
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 08/05/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H7) Quarter corner common to Sections 15 and 22. Corner previously approved 12/22/95 by Luce Co. Remonumentation Peer Review and recorded 2/29/1996 in Liber 2, Luce County Land Corner Records, Page 668.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H7) On April 21, 2008, found the monument of record in place, in good condition, and at record bearing and distance from the four Sugar NBTs listed in Part C of the 1995 record. In anticipation of road construction, made three additional witnesses (described below). By August 5, 2008 the monument and three of the 1995 witnesses had been destroyed by road construction. On that date, I reestablished the corner position at the 1995 position, at record bearing and distance from the remaining 1995 witness 10" Sugar Maple N12W (N13W M), 16.82' (16.82' M) and from the new witnesses marked in April.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H7) Set 5/8"x24" rebar with plastic cap stamped MICH DNR LS33986, buried below ground surface. Set measuring nail with MDNR tag in the side of the following three witness trees.
 7" Maple N46E 26.02' mrkd "1/4S NBT"
 10" Maple S45W 67.86' do
 6" Maple S26E 52.84' do
 10" Maple N13W 16.82' Fd. nail/tag #27450
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 02/17/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971