

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 45N R 11W	G7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 04/21/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G7) Corner common to Sections 15-16-21-22. Corner previously approved 12/22/95 by Luce Co. Remonumentation Peer Review and recorded 2/29/96 in Liber 2, Luce County Land Corner Records, Page 667.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G7) Found the 2" pinched top pipe monument of record, in good condition, buried on the North side of an East-West road. The 6" squared wood post noted in the 1995 record as being set adjacent is now gone. The monument was found at record bearing and distance from two of the witnesses noted in Part C of the 1995 record. The 2" pipe N49E (N54E M) 43.65' (43.65' M) was found in good condition, and the 12" Y.Birch N41E 16.42' is now a 4' high stump with nail and tag in place. The other witnesses noted in the record have been destroyed by road construction. I accepted the 2" pipe and make this recording in order to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G7) Found 2" pinched top pipe on North side of East-West road. Set measuring nail with MDNR tag in the side of:  
 12" Maple N06E 37.12'      mrkd "S15 NBT"  
 8" Maple S30W 77.48'      "S21 NBT"  
 16" Maple S04E 32.65'      "S22 NBT"  
 Fd. 2" pipe N54E 43.65'  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 02/17/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities