

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970  
Two Corners

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 12 W.	A-12 5, Sec. 31
2. PROPERTY CONTROLLING IN SECTION 31	T. 45 N. R. 12 W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 7/13 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
 A-12 Corner, on Westside, Sec. 31, set by John Burt, D.S. for Wm. A. Burt, D.S. in 1841, while running the Range Line.  
 Bearings were:

Hemlock 9" N23°E 9 lks  
 Spruce 10" N11°W 11 lks

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 A-12 Found Squared wood post with remains of a hemlock stump in proper position. Found blazes to North, South and West of corner.

5, Sec. 31 Found 3/4" Iron, buried in road by Frank Burgess, R.L.S. Found concrete 1st monument, 33.0' East of corner for a witness. Corner is 1319.3' South of North 1/4 Cor., Sec. 31.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 A-12 Placed 1" pipe with 4" aluminium cap at corner.  
 New Bearings:

12" Cedar N74°W 12.3'  
 14" Cedar N51°E 24.0'

5, Sec. 31 Recorded corner as located,  
 Witness:  
 4" Concrete Flat Monument, East, 33.0'

SIGNED BY Billy D. Buckler DATE 8/2/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)