

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Two Corners

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. 9. R. 12 E.	A-11 B-11
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S. R. _____ E. _____ W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 7/24 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

A-11 Sec. Cor. 30-31, on West Twp. Boundary, placed by John Burt, D.S. in 1841, while running this Range Line.

Bearings were:

Cedar 10" S73°W 16 lks and Cedar 10" N36°W 17 lks and
Spruce 15" N38°E 17 lks.

B-11 1/4 Cor. bet. Secs. 30-31, set by Guy H. Carleton, D.S., 1849.

Bearings were:

Sugar 10" N68°E 20 lks
Sugar 6" S79°W 31 lks

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-11 Corner re-established at intersection of old blazed lines to North, South, East. An old log road and watering hole may have obliterated any original evidence.

B-11 Found an Iron Bolt, buried in center of N-S Road.

Corner lies 27.9' South of Power Line.

Half mile to West measured 2542.6'; Record indicates 2605.0'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Placed 1" piep with 4" Aluminium cap at corner.

New Bearings:

12" Soft Maple N46°E 38.9'
12" Soft Maple N8°W 40.1'

B-11 Re-witnessed Corner.

New Bearings:

16" Hard Maple S39°E 53.7'
18" Hard Maple S22°W 60.1'

SIGNED BY Billy D. Buckler DATE 8/2/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8827 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____