

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co. Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. <u>45</u> N. S. R. <u>12</u> E. W.	G-3, I-3	
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S. R. _____ E. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 6/18 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corners set originally by Guy H. Carleton, D.S. in 1849.

- G-3 Sec. Cor. 3-4-9-10,
Bearings were: Cedar 10" $N45^{\circ}W$ 8 lks. and Cedar 8" $S35^{\circ}E$ 7 lks.
- I-3 Sec. Cor. 2-3-10-11,
Bearings were: Beech 10" $S55^{\circ}W$ 51 lks. and Beech 12" $N61^{\circ}E$ 29 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-3 Corner replaced at wood post, set by unknown persons. Found numerous cedar stumps. I did find two cedar stumps which agree with the record for size, bearing and distance, old scars but find no marks. Position is 33.0' North and 9.0' West of Corner.
- I-3 Corner re-established by Double proportionate measure bet. Cors., 1 mile North, 1/2 mile South, 1 mile West, and 1 mile East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-3 Placed 1" pipe with 4" aluminium cap.
New Bearings:
9" Cedar West 40.3'
9" Soft Maple $S47^{\circ}E$ 48.5'
- I-3 Placed 1" pipe with 4" Brass Cap.
New Bearings:
8" Soft Maple $S11^{\circ}E$ 23.2'
10" Soft Maple $N76^{\circ}W$ 20.2'

SIGNED BY Billy D. Buckler DATE 6/27/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____