

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Loc. Co. _____

To Corners. _____

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. S. R. 12 E. W.	I-4, 7-Sec. 10
2. PROPERTY CONTROLLING IN SECTION	10, T. 45 N. S. R. 12 E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 6-29 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and, or subsequent restoration:

1-4 _____ 2" Cor. Bat. Secs. 10-11; set by Guy H. Carleton, D.S. in 1849.
 7-Sec. 10 _____ Cedar 12", 215", 48 1/2", and Cedar 9", 210", 28 1/2".
 7-Sec. 10 _____ Cedar 12", 215", 48 1/2", and Cedar 9", 210", 28 1/2".

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

1-4 _____ 1" _____ 4" _____ old wood post. Found numerous cedar stumps in area but could identify none, with certainty. Distance North to Swamp edge checks well. Found old blazes, running East and West, a few feet South of corner.
 7-Sec. 10 _____ Corner placed by single proportionate measure bet. Sec. Cor. to North and Cor. to South.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-4 _____ 1" _____ pipe with 4" aluminum cap at both corners.
 1-4 _____ New bearings: 8" Cedar, S45°E, 9.6' and 6" Cedar, N57°W, 20.2'
 7-Sec. 10 _____ New bearings: 7" H. Maple, N35°W, 22.5' and 10" Basswood, S30°E, 28.2'

SIGNED BY Billy D. Buckler
 Billy D. Buckler

DATE 9-26-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8267



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____