

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>45</u> N. <u>X</u> R. <u>12</u> <u>K</u> <u>W</u>	J-1, I-1
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-26-80, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

J-1 Quarter Corner on North side of Section 2, set by Wm A. Burt, D.S. in 1841.  
Bearings were: Beech 16", N10°E, 10 lks. & Sugar 22", N49°W, 34 lks.

I-1 Section Corner bet. Sec's. 2-3 on North boundary of township, set by Wm A. Burt, D.S. in 1841. Bearings were:  
1841 Bearings: Beech 22", N75°E, 44 lks. & Beech 30", N7°W, 36 lks.  
1849 Bearings: Beech 10", S33°W, 25 lks. & Beech 6", S41°E, 43 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J-1 Placed 1/4 corner midway between two section corners. Found a meandering fence line about 30' West of corner. No original evidence.

I-1 Found 4" Concrete Plat Monument set by Tom Beaudrie, in center of road and in line with fence to South and East. Found 1 1/2" Iron Pipe, 33.0' East of corner. Also found 5/8" Iron Pipe in ground.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 Placed 1" pipe with 4" aluminium cap at corner. New Bearings are:  
9" S. Maple, S18°E, 23.4'. & 9" S. Maple, N57°W, 16.5' & 7" H. Maple, N21°E, 22.0'

I-1 Witnessed corner as monumented. New Bearings are:  
14" H. Maple, N82°E, 23.9' & 12" H. Maple, N37°E, 35.7'.

SIGNED BY Billy D. Buckler DATE 8-1-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET