

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co. 3 Corners

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <u>12</u> <u>W.</u> <input checked="" type="checkbox"/>	K-2
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>45</u> N. <u>12</u> <u>W.</u> <input checked="" type="checkbox"/>	9-Sec. 2, 2-Sec. 2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-26, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- K-2 Quarter Corner bet. Sec's. 1-2, set by Guy H. Carleton, D.S. in 1849. Bearings: Beech 14", N74°W, 38 lks. & Beech 12", S21°E, 37 lks.
 - 9-Sec. 2 East 1/16 Corner of Section 2.
 - 2-Sec. 2 East 1/16 Corner on North side of Section 2.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- K-2 Restored corner by single prop. meas. bet. two sec. cors. Found no evidence of original corner. A fence corner found 32.7' West and 40' North of corner location. Corner is on East edge of a small clearing.
 - 9-Sec. 2 Placed corner midway bet. Center Corner and the East 1/4 corner.
 - 2-Sec. 2 Placed corner midway and on line bet. Sec. Cor. to East and 1/4 cor. to West. Corner is 2.0' West and 5.6' South of a fence cor. Another fence corner is 26.4' South and 25.0' East of Corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at all three corners. New Bearings are:
- K-2 6" H. Maple, S4°W, 38.9' & 16" Beech, N85°E, 21.5' & 9" Beech, N6°W, 39.8'.
 - 9-Sec. 2 9" H. Maple, S41°E, 14.4' & 8" S. Maple, N74°W, 13.3' & 8" S. Maple, N2°E, 18.7'
 - 2-Sec. 2 8" H. Maple, S81°E, 26.2' & 8" H. Maple, S65°W, 28.1' & 6" H. Maple, N67°W, 26.1'

SIGNED BY Billy D. Buckler DATE 8-1-80
Billy D. Buckler
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET