

Luce County Remonumentation Program

1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Luce _____ Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 45N R 12W H-7
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Filed 12-22 A.D., 1993

At 10:00 o'clock A. M.

Liber 2
File No. page 517

Walter S. Mahan
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on November 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(H-7) 1/4 Corner Sections 15 & 22, T45N-R12W

1849: Corner established by Guy H. Carleton
Set 1/4 Section Post
Sugar 14 N 62 E 5 links
Beech 8 S 14 W 33 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner reestablished as part of the Luce County Remonumentation Program.

Found a North-South fence line on the South side of the road. A prorated position for the corner position falls on the extension of fence line. Reestablished corner position midway and on line between the Northeast and Northwest corners of Section 22.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner is a 1/2" x 24" iron with a 3 1/4" diameter stamped aluminum cap, 6" below gravel road surface. Falls 1' North of centerline County Road 436 (East-West, gravel). Falls on extension of fence line to the South.

7" Balsam Fir	N56°E	77.67'
8" Yellow Birch of Twin	S38°E	55.94'
15" Maple	S16°W	43.08'
18" Beech	S45°W	60.32'
16" Balsam Fir	N14°W	29.40'



Signed by William L. Karr Date 12/16/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination. Distances are to a nail with P.S. 27450 tag in side of witness objects unless noted.