

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T 45N R 12W	A11	
	T 45N R 13W	M11	
	T _____ R _____	(same corner)	
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3									
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	20	21	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 02/05/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A11) Corner common to Sections 30-31 T45N-R12W (Luce County) and Sections 25-36 T45N-R13W (Schoolcraft County). 1999 - Approved by Luce Co. Remonumentation Program, Rec. in L.3, P.888, Luce Co. Records. Found 1" pipe with 4" aluminum D.N.R. cap as recorded by Buckler in 1972. Accepted corner position as found. Red Maple 14" N06E 37.08', Red Maple 16" N40E 39.32', Spruce 9" S76E 24.92', Balsam 8" N35W 34.32', Red Maple 14" N12W 40.64'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A11) Found the MDNR monument of record, in good condition, and at record bearing and distance from the 1999 NBTs. The Red Maples NE are in good condition. The Spruce SE is a stump, the Balsam NW is dead and down, the Red Maple NW is a stump. This corner is being recorded to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A11) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Birch S08E 24.6' mrkd "S31 NBT"
 7" Maple N41W 39.4' "S25 NBT"
 The 1999 NBTs were found as follows:
 Red Maple 14" N16E 37.08' mrkd "S30"
 Red Maple 16" N51E 39.4' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 02/23/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities