

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S <u>2</u> T <u>45N</u> R <u>12W</u>	<u>E-E 1/64</u>	
	S <u>2</u> T <u>45N</u> R <u>12W</u>	<u>C-E-SE 1/64</u>	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3										4			
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 06/04/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-E 1/64 corner between Sec. 2 and 11) - 1/64 corner being the SE corner of the W1/2 of the SE1/4 of the SE1/4 of Sec. 2. Not established in the original survey.

(C-E-SE 1/64, Sec. 2) 1/64 corner being the NE corner of the W1/2 of the SE1/4 of the SE1/4 of Section 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-E 1/64) Established the corner midway and on the Section line between Section corner K3 658.85' east and 1/16 corner #16 of Sec.2 (unmonumented), 658.85' west. The corner falls in the north shoulder of a dirt road.

(C-E-SE 1/64) Established the corner midway and on the 1/16 line between 1/16 corners #13 and #14, Section 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-E 1/64) Set 1"IDx36" I.pipe with plastic MDNR cap. Set meas. nail with MDNR tag in the side of:
 11" Maple N80W 4.65' mrkd "1/64 BT"
 10" Sugar N05W 14.15' do
 8" Maple clump N73W 34.5' do
 5" twin Sugar S17E 25.3' do
 Bearings are magnetic.

(1/64) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Maple N20W 7.3'
 8" Maple N29E 14.0'
 7" Maple S40E 8.35'
 7" Maple S49W 16.95'
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/13/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

