

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>45N</u> R <u>12W</u>	<u>I2</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 05/07/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I2) Quarter corner common to Sections 2 and 3. 1849 - Established by Guy Carleton Deputy Surveyor on the Section line between Section corners 39.62 chains north and 40.00 chains south. Set post. Cedar 10" N39W 21 links, Cedar 8" S74E 08 links. 1973 - Original corner position perpetuated by Billy D. Buckler RLS, who found remains of Cedar BT N39W 21 links, down with both faces complete with scribe marks. Set 1" pipe with 4" aluminum cap at the corner position. New BTs: 11" Cedar East 14.7', 10" Cedar N27W 13.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I2) Found the 1973 monument with wood post adjacent, in good condition and at record bearing and distance from the 1973 NBT Cedar East 14.7', in good condition, and from the rotted stump remains of the OBT Cedar N39W 21 links. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I2) Found 1" ID I. pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 14" Cedar S88E 15.0' open blaze 1973 NBT
 10" Cedar S40E 25.85' mrkd "1/4S NBT"
 14" Cedar N83W 27.5' do
 16" Cedar N18E 30.9' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 08/13/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities