

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 12W	J3
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 2 T 45N R 12W	9
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2	●		1	
3										●			
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 9 06/08/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J3) Quarter corner common to Sections 2 and 11. 1973 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1" ID I.pipe with 4" aluminum cap. 7" Maple N71E 26.2', 7" Maple S18W 28.8'.

(9-Sec. 2) East 1/16 corner, Section 2. 1980 - Established by Billy D. Buckler RLS midway and on line between 1/4 corner 1320.0' east and the intersection of 1/4 lines of Section 2 1320.0' west. Set 1" ID I.pipe with 4" aluminum cap. 9" Sugar S41E 14.4', 8" Maple N74W 13.3', 8" Maple N02E 18.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J3) Recovered the 1973 monument in good condition and at record bearing and distance from the 1973 witnesses, both in good condition. Used the position of this monument to subdivide Section 2 this date.

(9-Sec. 2) Found the 1980 monument in good condition and at record bearing and distance from the 1980 witnesses. The Maple NE is a stump. The two other BTs are in good condition. The position of the monument was found to be 3.1' south and 1.8' west of the record position and I accepted same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J3) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" Maple S22W 29.4' mrkd "1/4S" 1973 NBT
 10" Maple N76E 26.55' do do
 9" Maple S70W 20.8' mrkd "1/4S NBT"
 7" Maple N11W 29.5' do
 Bearings are magnetic.

(9) Fd. 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" Maple N69W 13.55' mrkd "E1/16" 1980 BT
 16" Sugar S38E 14.5' do do
 11" Sugar S69E 21.35' mrkd "E1/16"
 8" Sugar S39W 40.5' mrkd "E1/16 BT"
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/13/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities