

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S <u>2</u> T <u>45N</u> R <u>12W</u>	<u>J2</u>	_____
	S <u>2</u> T <u>45N</u> R <u>12W</u>	<u>14</u>	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3					1
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 06/04/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(J2) Center of Section 2. Not established in the original survey. 1980 - Billy D. Buckler RLS computed the location for the corner but did not monument it during his partial subdivision of this section.

(14-Sec. 2) South 1/16 corner between Sections 1 and 2. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(J2) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(14-Sec. 2) Established the corner midway and on the Section line between Section corner 1329.83' south and Quarter corner 1329.83' north.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(J2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" Maple S39E 9.2' mrkd "CS BT"  
 7" Balsam N04E 6.5' do  
 16" W.Birch S65W 36.15' do  
 12" Maple S68E 19.6' do  
 Bearings are magnetic.

(14) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" Maple N76E 6.85' mrkd "S1/16 BT"  
 6" Sugar S35E 8.8' do  
 12" Maple S28W 26.95' do  
 7" twin Sugar S85W 27.3' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 08/13/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

