

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u>	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T 46N R 8W	L13	
	T 45N R 8W	L1 (same corner)	
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

T46N R08W

I, Stephan J. Szyszkoski, in a field survey on 03/31/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L13) Quarter corner common to Section 36 T46N-R08W and Section 1 T45N-R08W. 1840 - Established by Wm.A.Burt Deputy Surveyor midway and on the Township line between Township corner 40.00 chains east and Section corner 40.00 chains west. Set post. Spruce 6" N02E 14 links, Spruce 4" N30W 25 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L13) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the curved Township line between Section corners of record 2630.31' east and west. The true bearing of the Township line was observed to be within 30 arc seconds of cardinal.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 4" Tamarack N20W 6.65' mrkd "1/4S NBT"
 5" B.Spruce S59W 24.25' do
 4" B.Spruce S04W 45.12' do
 6" Tamarack S50E 69.44' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 08/25/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities