

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY-----	T. <u>46</u> N. <u>X</u> R. <u>9</u> W.	G-4
2. PROPERTY CONTROL- ING IN SECTION-----	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION-----	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**REGISTER OF DEEDS STAMP AND
FILING NUMBER**

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 1/24 1968, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Original $\frac{1}{4}$ Corner bet. Secs. 9-10 set by Harvey Mellen, D.S. 1850.

Bearings were:
W. Pine 36" S22°E 16 Links
Hemlock 8" N29°W 22 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner replaced as set by H.C. Lawrence, R.L.S.

Found a W. Pine Stump in proper location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminum cap at corner.

New Bearings:
9" B. Spruce S10°E 8.5'
10" Soft Maple N51°E 14.2'

SIGNED BY Billy D. Buckler DATE 6/28/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____
APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)