

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Luce COUNTY


T 46N R 9W

DESCRIPTION OF CORNER Sec Cor. common to Secs. 4-5-8-9.

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9-16-71

WITNESSES TO CORNER..... 9" Red Pine (s8 NBT) South 9.6'



6" Jack Pine (s5 NBT) $N44^{\circ}W$ 36.2'

7" Jack Pine (s4 NBT) $N54^{\circ}E$ 27.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.
This corner placed by proportionate measure, between corners; one mile north
and one mile south. Distance to marshes to east and west and south check
with the record. Found blazes to east. Found no evidence of the pine witnesses.

Found a post and fence corner, 60.0' south and 64.0' east which was not accented
as the corner location.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 12-7-71

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68