

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Luca COUNTY


T 46N R 9W

DESCRIPTION OF CORNER North 1/16 corner bet. Secs. 9-10

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11/12/71

WITNESSES TO CORNER..... 20" W. Pine (N1/16 BT) N72°E 30.3'



8" Cedar (N1/16 BT) N61°W 19.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.
Corner placed midway and on line bet. Sec. Cor. to north and $\frac{1}{2}$ Cor. to south.

Corner lies 50' South of an old woods road and 30' North of swamp.

SURVEYOR'S SEAL

Billy D. Buckler

DISTRIBUTION:

SIGNED Billy D. Buckler DATE 12-7-71
REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68